시 방 서

업체명 : ㈜한울 청양공장

■ B 구역　냉난방기계 제작 및 설치공사(37평)

품　　명	규　　격	단위	수 량
RECIPROCATING COMPRESSOR UNIT		SET	1
- POWER: ∮3*380V*60Hz*4P*15HP			
- TEMPERATURE:CT/+50℃, ET/0℃			
- CAPACITY:30,000Kcal/h			
- SINGLE STAGE SEMI HERMETIC RECIPROCATING COMPRESSOR(Bitzer-4PE-15Y)			
AIR COOLED CONDENSER 25RT		SET	1
AUTO CONTROL PANEL		SET	1
CONTROL WIRING		LOT	1
SOLENOID VALVE	5/8B	EA	2
EXPANSION VALVE	6.0RT	EA	2
REFRIGERANT PIPE & FITTING'S		LOT	1
WATER PIPE & FITTING'S & HANGER		LOT	1
배관보온(아마플렉스)		LOT	1
OTHER'S MATERIAL		LOT	1
REFRIGERANT GAS	R-404A	B/T	3
MAN POWER(숙식비 포함)		M/D	
공사경비			

■ D 구역 냉난방기계 제작 및 설치공사(78평)

품 명	규 격	단위	수 량
RECIPROCATING COMPRESSOR UNIT		SET	1
- POWER: ∮3*380V*60Hz*4P*30HP			
- TEMPERATURE:CT/+50℃, ET/0℃			
- CAPACITY:60,000Kcal/h			
- SINGLE STAGE SEMI HERMETIC RECIPROCATING COMPRESSOR(Bitzer-4GE-30Y)			
AIR COOLED CONDENSER 40RT		SET	1
AUTO CONTROL PANEL		SET	1
CONTROL WIRING		LOT	1
SOLENOID VALVE	5/8B	EA	3
EXPANSION VALVE	6.0RT	EA	3
REFRIGERANT PIPE & FITTING'S		LOT	1
WATER PIPE & FITTING'S & HANGER		LOT	1
배관보온(아마플렉스)		LOT	1
OTHER'S MATERIAL		LOT	1
REFRIGERANT GAS	R-404A	B/T	6
MAN POWER(숙식비 포함)			
공사경비			